BREEZY BOYS'

MECHANICAL

DATE
Wed, April 1st, 2026

VANSCOY SCHOOL
309 Main St
Vanscoy S0L 3J0

Breezy Boys' Mechanical
7777 De Calier Blvd
Montreal, Quebec
306- 752- 4545
H4P 2H2
Breezyboysmechanical@gmail.com

Vanscoy school installation project bid

Owner/ employees part of the project

Aidan McInnes – Owner/ operator
Darian Chow- Executive outside sale representative
Hassan – Digital marketing and analytics
Nate – Executive sanitation engineer

About us

Here at Breezy Boys Mechanical, we have a combined experience of 24 years in the field; we are committed to providing quality HVAC and refrigeration services. The work in which we specialize in both commercial and residential environments is important. Our company's hands-on team provides installation, maintenance, and service for your home or business. As a growing company, we seek to change the landscape of service providers in Saskatchewan. Our main goal is to provide high quality work at an affordable price.

Table of contents

- (Pages 1 – 2) – pricing of material, unit, delivery labor, crane fee
- (Pages 3 – 4) – Contract and agreement for installation and teardown
- (Page 5) – A laid out time schedule for finishing the job
- (Page 6) – Isometric drawing of the unit and piping diagram

Breezy Boys Mechanical – Vanscoy school installation project bid

Cost and quantity of material used

Quantity	Type of material used	Base cost	Total cost
1	12’ length of ¾” copper type L	$91.77	$91.77
6	12’ length of 1 3/8” copper type L	$150.31	$901.83
3	12’ length of 2 1/8” copper type L	$290.94	$871.47
1	¼” soft copper roll	$85.10	$85.10
4	¾” long radius elbow	$6.10	$24.38
12	1 1/8” long radius elbow	$15.76	$189.06
10	2 1/8” long radius elbow	$89.00	$890.00
2	2 1/8” long radius street elbow	$75.67	$151.34
8	1 1/8” coupling	$5.06	$40.48
5	2 1/8” coupling	$23.14	$115.70
2	1 1/8” tee	$23.58	$47.15
1	2 1/8” tee	$47.38	$47.38
2	2 1/8” to 1 5/8” reducing coupling	$29.79	$59.57
6	7/8” to ¾” bushing	$3.45	$20.70
2	1 1/8” to ¾” bushing	$7.94	$15.87
2	1 1/8” vibration absorber	$143.98	$287.96
1	2 1/8” vibration absorber	$338.00	$338.00
2	7/8” solenoid valve	$439.53	$879.06
1	1 1/8” solenoid valve	$736.00	$736.00
3	MKC-2 coils	$191.00	$571.00
2	¾" ball valve	$114.20	$228.40
2	7/8” sight glass	$104.00	$208.00
2	¾" strainer	$402.20	$802.40
2	C-307-S filter drier	$137.83	$275.66
2	OVE15VC TXV	$237.49	$474.98
1	Discharge bypass valve	$506.40	$506.40
6	2 1/8” tubing by 1” wall Armaflex	$106.80	$640.80
6	1 1/8” tubing by ½" wall Armaflex	$26.64	$159.84
4	¾" cush clamp	$15.36	$61.44
16	1 1/8” cush clamp	$13.80	$220.80
8	2 1/8” cush clamp	$21.36	$170.88
2	2 1/8” PVC sleeve	$30.00	$60.00
1	4 1/8” PVC sleeve	$49.50	$49.50

3(lb)	silfos	$187.50	$187.50
2	OM5 sand cloth	$23.76	$47.52
2	1 5/8” Unistrut	$62.04	$124.08
4	10’ length of 3/8” threaded rod	$14.00	$56.00

Breezy Boys Mechanical – Vanscoy school installation project bid

Cost and quantity of material used (continued)

Quantity	Type of material used	Base cost	Total cost
1	100 pack of self-tapping 5/16” x 1”	$35.00	$35.00
8	Roof blocks	$18.72	$149.76
1	520 adhesive paints	$31.92	$31.92
4	25 (lb) R410a tanks	$5500.00	$5500.00
2	Fire seal tube	$22.00	$44.00
2	acetylene	$125.00	$250.00
5	Nitrogen tanks	$100.00	$500.00
1	100 pack of 3/8” nuts	$26.00	$26.00
10	Ceiling flange	$4.92	$49.20
	Total cost of all materials		$17,246.84

Delivery fee of the unit and crane lift

Delivery fee for transporting the unit- $500.00

Crane Lift ($350.00 an hour) – we will be using the crane for 3 hours - $1050

Labor length and cost

The installation and tear down of the old equipment will roughly take 80 hours to get the job done. And then 16 hours for contingencies. Here at breezy boy's mechanical, we charge $129 an hour for labor; we will need two guys to remain the whole time. ($129 x 96 = $12,384 x 2 = $24768.00) will be the total labor charge.

Condensing unit cost

30 Ton Trane RAV C20-1, - $40,000.00

Total cost of installation and materials

Sub Total: $83,564.84

GST: $4,178.24

PST: $5,013.89

Total: $92,756.97

Breezy Boys Mechanical – Vanscoy school installation project bid

HVAC Condenser replacement agreement

This Agreement is made on Wed, April 8th, 2026
Contractor: Breezy Boys Mechanical
7777 De Calier Blvd, Montreal, Quebec
H4P 2H2
(306) - 713 – 6573
Vanscoy school, 309 Main street, Vanscoy, Saskatchewan
S0L 3J0

1. Scope of work

The contractor agrees to supply and install a new air conditioning condenser unit at Vanscoy School. The scope of work includes:

- Removal and proper disposal of existing condenser unit
- Installation of refrigeration piping and necessary components
- Pressure testing, evacuation, and charging of the system
- System startup and operational testing

Exclusion: All electrical work, including wiring, disconnects and connections, is to be completed by others. Structural, roofing, or crane services unless otherwise specified.

2. Contract price

The total contract price for the work described above is: $83,564.84 + tax (CAD)

3. Payment Terms

Deposit: 25% due upon acceptance of this agreement can phone or email us to deposit.
Final payment: due upon substantial completion of work. Late payments may be subject to interest charges of 5% per month

4. Schedule

Estimate start date: We can start any time after April 15th. Just give us a couple days' notice so we can prepare. If we were to start April 15th we should be done April 21st. Timelines may be affected by weather, material availability, or unforeseen site conditions.

5. Responsibilities

Contractor responsibilities: Perform all work in a professional and workman like matter. Comply with applicable codes and regulations. Maintain a safe work environment.
Client responsibilities: Provide site access during normal work hours. Ensure electrical work is completed by qualified personnel prior to startup. Obtain any required permits unless otherwise agreed.

6. Warranty

We at Breezy Boys Mechanical offer 1 year labor warranty from the day we finish the installation.
Equipment warranty: provided by manufacturer of the unit (typically 5-year warranty)
Warranty does not cover misuse, lack of maintenance, or unauthorized modifications.

7. Changes in work

Any changes or additional work must be agreed upon in writing and may result in additional charges or schedule adjustments

8. Liability

The contractor shall not be liable for delays or damages caused by factors beyond their control, including but not limited to weather, supply chain issues, or third-party contractors.

9. Termination

Either party may terminate this agreement with written notice. The client agrees to pay for all work completed and materials supplied up to the termination.

10. Acceptance

By signing below, both parties agree to the terms outlined in this agreement.

Contractor: Breezy Boys Mechanical
Name:

Signature:

Date:

Client: Vanscoy School

Name:

Signature:

Date: